



PTT PHENOL COMPANY
LIMITED

PROCESS SPECIFICATION

CUMENE COLUMN REBOILER CONDENSATE POT (D-2121)

Docu. No. : 14780-8120-PS-D2121
Project No. : 120117
Rev. No. : Z1
Date : MAY 10, 2016
Page : 1 / 4

TITLE :

CUMENE COLUMN REBOILER CONDENSATE POT

(D-2121)

DISCIPLINE : PROCESS
DOCUMENT NO. : 14780-8120-PS-D2121
PROJECT NAME : PTT Phenol Train II Project
PROJECT NO. : 120117
OWNER : PTT Phenol Company Limited (PPCL)

Z1	MAY 10, 2016	AS BUILT	S.W.Park	J.S.Chung	-	S.W.Lee
F1	MAY 22, 2014	FINAL ISSUE	S.W.Park	J.S.Chung	-	S.W.Lee
A3	APR 18, 2014	APPROVED FOR DESIGN	S.W.Park	J.S.Chung	-	S.W.Lee
A2	DEC 11, 2013	APPROVED FOR DESIGN	S.W.Park	J.S.Chung	-	S.W.Lee
A1	OCT 2, 2013	APPROVED FOR DESIGN	S.W.Park	J.S.Chung	-	S.W.Lee
O1	JUN 27, 2013	COMMENT ISSUE	S.W.Park	J.S.Chung	-	S.W.Lee
REV. NO.	DATE	DESCRIPTION	PREP'N	REVIEW	QA REVIEW	APPROVAL
REV. NO.	PREPARATION DEPT.	PREPARATION	REVIEW	QA REVIEW	APPROVAL	
Z1	PROCESS	S.W.Park	J.S.Chung	-	S.W.Lee	
		MAY 10, 2016	MAY 10, 2016	-	MAY 10, 2016	

This Document is the property of POSCO Engineering Co., Ltd. Therefore, it shall not be released to Any third party without permission of an authorized personnel of the POSCO Engineering Co., Ltd.

[illegible]



Note: The information in this document is confidential and the property of UOP LLC and must not be disclosed to others or reproduced in any manner or used for any purpose whatsoever without its written permission.



VESSELS

PROJECT SPECIFICATION

963764 — 301

SHEET 3 / 4

REV	DATE	BY	APVD	REV	DATE	BY	APVD
0	12APR12	ANJ	MEH				

General Notes

- A. Vessels shall be constructed in accordance with the following unless otherwise specified on the individual vessel specification sheet.

Standards:

UOP Standard Specification	3-11
UOP Standard Drawing	8-121

- B. Although the resulting inside diameter may be slightly different than specified, vessels without trays or packing, may be fabricated from pipe.
- C. The dimensioned location of some of the vessel level nozzles may be noted as min (minimum) or max (maximum). It is the responsibility of the contractor to adjust these dimensions to suit the specific level requirements specified on the UOP Piping and Instrument Diagram(s) and on UOP Standard Drawing 8-121. When additional nozzles are required for level instrumentation, the contractor shall specify them consistent with the size, class and facing requirements specified in the UOP Project Specification 301-Vessels and on the UOP Piping and Instrument Diagram(s).
- D. When system of measurement is metric, all dimensions are in millimeters unless noted otherwise.
- E. Contractor shall not locate TI thermowells in a downcomer. Contractor shall also ensure that TI thermowells are located to avoid interference with downcomers, weirs, distributors, collectors, baffles, chimneys, traps and all other vessel internals.
- F. Existing Unit 1 vessel design for this service has been reused with only small or no changes and should be considered for this vessel.
- G. For Trays and Packed-bed Columns the distance from the bottom of the bottom head to the center line of the lower manway shall not exceed 3000 mm.

Other specifications
referenced in this
specification:

UOP Standard Specification: 3-11, 3-37, 3-38

UOP Standard Drawing: 3-115, 3-122, 3-123, 3-144, 3-150, 3-160, 3-162, 3-183, 3-185, 3-192, 3-270, 3-288,
3-290, 3-312, 3-331, 3-337, 3-435, 8-121

UOP Project Specification: 963764-106, 963764-307

VESSEL DATA SHEET

[illegible]