



PTT PHENOL COMPANY
LIMITED

PROCESS SPECIFICATION

PIPB COLUMN REBOILER CONDENSATE POT (D-2122)

Docu. No. : 14780-8120-PS-D2122
Project No. : 120117
Rev. No. : Z1
Date : MAY 10, 2016
Page : 1 / 4

TITLE :

PIPB COLUMN REBOILER CONDENSATE POT

(D-2122)

DISCIPLINE : **PROCESS**
DOCUMENT NO. : **14780-8120-PS-D2122**
PROJECT NAME : **PTT Phenol Train II Project**
PROJECT NO. : **120117**
OWNER : **PTT Phenol Company Limited (PPCL)**

Z1	MAY 10, 2016	AS BUILT	S.W.Park	J.S.Chung	-	S.W.Lee
F1	MAY 22, 2014	FINAL ISSUE	S.W.Park	J.S.Chung	-	S.W.Lee
A3	APR 18, 2014	APPROVED FOR DESIGN	S.W.Park	J.S.Chung	-	S.W.Lee
A2	DEC 11, 2013	APPROVED FOR DESIGN	S.W.Park	J.S.Chung	-	S.W.Lee
A1	OCT 2, 2013	APPROVED FOR DESIGN	S.W.Park	J.S.Chung	-	S.W.Lee
O1	JUN 27, 2013	COMMENT ISSUE	S.W.Park	J.S.Chung	-	S.W.Lee
REV. NO.	DATE	DESCRIPTION	PREP'N	REVIEW	QA REVIEW	APPROVAL
REV. NO.	PREPARATION DEPT.	PREPARATION	REVIEW	QA REVIEW	APPROVAL	
Z1	PROCESS	S.W.Park	J.S.Chung	-	S.W.Lee	
		MAY 10, 2016	MAY 10, 2016	-	MAY 10, 2016	

This Document is the property of POSCO Engineering Co., Ltd. Therefore, it shall not be released to Any third party without permission of an authorized personnel of the POSCO Engineering Co., Ltd.

[illegible]



Note: The information in this document is confidential and the property of UOP LLC and must not be disclosed to others or reproduced in any manner or used for any purpose whatsoever without its written permission.



VESSELS

PROJECT SPECIFICATION

963764 — 301

SHEET 3 / 4

REV	DATE	BY	APVD	REV	DATE	BY	APVD
0	12APR12	ANJ	MEH				

General Notes

- A. Vessels shall be constructed in accordance with the following unless otherwise specified on the individual vessel specification sheet.

Standards:

UOP Standard Specification	3-11
UOP Standard Drawing	8-121

- B. Although the resulting inside diameter may be slightly different than specified, vessels without trays or packing, may be fabricated from pipe.
- C. The dimensioned location of some of the vessel level nozzles may be noted as min (minimum) or max (maximum). It is the responsibility of the contractor to adjust these dimensions to suit the specific level requirements specified on the UOP Piping and Instrument Diagram(s) and on UOP Standard Drawing 8-121. When additional nozzles are required for level instrumentation, the contractor shall specify them consistent with the size, class and facing requirements specified in the UOP Project Specification 301-Vessels and on the UOP Piping and Instrument Diagram(s).
- D. When system of measurement is metric, all dimensions are in millimeters unless noted otherwise.
- E. Contractor shall not locate TI thermowells in a downcomer. Contractor shall also ensure that TI thermowells are located to avoid interference with downcomers, weirs, distributors, collectors, baffles, chimneys, traps and all other vessel internals.
- F. Existing Unit 1 vessel design for this service has been reused with only small or no changes and should be considered for this vessel.
- G. For Trays and Packed-bed Columns the distance from the bottom of the bottom head to the center line of the lower manway shall not exceed 3000 mm.

Other specifications
referenced in this
specification:

UOP Standard Specification: 3-11, 3-37, 3-38

UOP Standard Drawing: 3-115, 3-122, 3-123, 3-144, 3-150, 3-160, 3-162, 3-183, 3-185, 3-192, 3-270, 3-288,
3-290, 3-312, 3-331, 3-337, 3-435, 8-121

UOP Project Specification: 963764-106, 963764-307

POSCO ENGINEERING

VESSEL DATA SHEET

PAGE : 4 of 4

CLIENT	: PTT PHENOL	REV.	DATE	REV.	DATE
JOB NAME	: PTT PHENOL TRAIN II PROJEC T	O1	JUN 27, 2013	F1	MAY 22, 2014
JOB NO	: 120117	A1	OCT 2, 2013	Z1	MAY 10, 2016
PLANT LOCATION	: MAP TA PHUT, THAILAND	A2	DEC 11, 2013		
REV DOC. NO	: 14780-8120-PS-D2122	A3	JAN 9, 2014		

Item No.	D-2122		Service	PIPB COLUMN REBOILER CONDENSATE POT	
No. Req'd	1 (ONE)		Type	Vertical	
Regulation			Code	ASME SECTION VIII DIV.1	

DESIGN CONDITIONS				
Fluid Name		Condensate		
Density at Oper. Temp. kg/m³		794.2		
Shell Inside Diameter mm		550		
Pressure	Oper.	40.0		
	kg/cm2g Design	50 / FV		
Temperature °C	Oper.	260		
	Design	300 / 120		
	MDMT	15		
Material	Shell	KCS		
	Head	KCS		
	INTL			
	Support			
Corrosion Allowance mm	Shell	3.0		
	Head	3.0		
	INTL			
PWHT		MR		
Radiograph		MR		
Joint Efficiency				
This Vessel is in the Following Service(s):				
Hydrogen		NO		
Hydrofluoric (HF) Acid		NO		
Hydrofluoric (HF) Acid (with Resid. Elem. Control)		NO		
Wet Hydrogen Sulfide (H2S)		NO		
Cyclic		NO		
Caustic		NO		
Carbonate		NO		
Amine		NO		
Vessel Heads :		2:1 ELLIP.		
Insulation :		H (50/70)		
Weight :		Empty ,Full		
NOZZLE SCHEDULE				
Mark	Qty.	Size	Rating & Facing	Service
AM	1	ID		MANWAY
AO	1	2"	300#, RF	EQUALIZING
-	-	-	-	-
BJ	1	3"	300#, RF	INLET
BK	2	2"	300#, RF	LG
BL	2	2"	300#, RF	LT
CW	1	3"	300#, RF	OUTLET

UNIT : mm

ACCESSORIES				

Notes

1. DELETED.

2. DELETED.

3. SPECIFIC GRAVITY : 0.8