



PTT PHENOL COMPANY
LIMITED

PROCESS SPECIFICATION

FEED WASH COLUMN (V-2201)

Docu. No. : 14780-8120-PS-V2201
Project No. : 120117
Rev. No. : Z1
Date : MAY 10, 2016
Page : 1 / 9

TITLE :

FEED WASH COLUMN

(V-2201)

DISCIPLINE : **PROCESS**
DOCUMENT NO. : **14780-8120-PS-V2201**
PROJECT NAME : **PTT Phenol Train II Project**
PROJECT NO. : **120117**
OWNER : **PTT Phenol Company Limited (PPCL)**

Z1	MAY 10, 2016	AS BUILT	S.W.Park	J.S.Chung	-	S.W.Lee
F1	MAY 22, 2014	FINAL ISSUE	S.W.Park	J.S.Chung	-	S.W.Lee
A3	APR 18, 2014	APPROVED FOR DESIGN	S.W.Park	J.S.Chung	-	S.W.Lee
A2	DEC 11, 2013	APPROVED FOR DESIGN	S.W.Park	J.S.Chung	-	S.W.Lee
A1	OCT 2, 2013	APPROVED FOR DESIGN	S.W.Park	J.S.Chung	-	S.W.Lee
O1	JUN 27, 2013	COMMENT ISSUE	S.W.Park	J.S.Chung	-	S.W.Lee
REV. NO.	DATE	DESCRIPTION	PREP'N	REVIEW	QA REVIEW	APPROVAL
REV. NO.	PREPARATION DEPT.	PREPARED BY	REVIEWED BY	QA REVIEW	APPROVED BY	
Z1	PROCESS	S.W.Park	J.S.Chung	-	S.W.Lee	
		MAY 10, 2016	MAY 10, 2016	-	MAY 10, 2016	

This Document is the property of POSCO Engineering Co., Ltd. Therefore, it shall not be released to Any third party without permission of an authorized personnel of the POSCO Engineering Co., Ltd.

[illegible]



PROJECT SPECIFICATION

963765 — **301**

SHEET 3 / 9



VESSELS

REV	DATE	BY	APVD	REV	DATE	BY	APVD
0	12APR12	TS	HDT				

General Notes

- A. Vessels shall be constructed in accordance with the following unless otherwise specified on the individual vessel specification sheet.

Standards:

UOP Standard Specification 3-11

- B. Although the resulting inside diameter may be slightly different than specified, vessels without trays or packing, may be fabricated from pipe.
- C. The dimensioned location of some of the vessel level nozzles may be noted as min (minimum) or max (maximum). It is the responsibility of the contractor to adjust these dimensions to suit the specific level requirements specified on the UOP Piping and Instrument Diagram(s) and on UOP Standard Drawing 8-121. When additional nozzles are required for level instrumentation, the contractor shall specify them consistent with the size, class and facing requirements specified in the UOP Project Specification 301-Vessels and on the UOP Piping and Instrument Diagram(s).
- D. When system of measurement is metric, all dimensions are in millimeters unless noted otherwise.
- E. Contractor shall not locate TI thermowells in a downcomer. Contractor shall also ensure that TI thermowells are located to avoid interference with downcomers, weirs, distributors, collectors, baffles, chimneys, traps and all other vessel internals.
- F. Suppliers (or equal):

Spray Nozzle:

BETE Fog Nozzle Inc.

www.bete.com

Profile Wire Screens:

Johnson Screens

www.johnsonscreens.com

Nagaoka International Corporation

www.nagaokajapan.co.jp

Other specifications
referenced in this
specification:

UOP Standard Specification: 3-11, 3-15, 3-35, 9-11

UOP Standard Drawing: 3-115, 3-116, 3-122, 3-123, 3-144, 3-183, 3-190, 3-264, 3-266, 3-313, 3-322, 8-121

UOP Project Specification: 963765-106, 963765-307

Note: The information in this document is confidential and the property of UOP LLC and must not be disclosed to others or reproduced in any manner or used for any purpose whatsoever without its written permission.



A Honeywell Company



VESSELS

REV

SERVICE	FEED WASH COLUMN	ITEM NO	V-2201
---------	------------------	---------	--------

Design	INT	15.0 kg/cm2(g)	@ 120° C
Conditions	EXT	FULL VACUUM	@ 250° C
at Top	Metal Temperature(Min)	15° C	
Operating	TOP	1.8 kg/cm2(g)	@ 39° C
Conditions	BTM	4.7 kg/cm2(g)	@ 41° C
Radiograph	MR		
Postweld Heat Treat	MR		

Material	Corrosion Allowance
SA 240 TYPE 304L, NOTE 2	1.5

This Vessel is in the Following Service(s):	
Hydrogen	- NO
Hydrofluoric (HF) Acid	- NO
Hydrofluoric (HF) Acid (with Resid. Elem. Control)	- NO
Wet Hydrogen Sulfide (H2S)	- NO
Severe Cyclic	- NO
Caustic	- YES
Carbonate	- NO
Amine	- NO
Note:	

Vessel Heads	
Top	2:1 ELLIPTICAL
Bottom	2:1 ELLIPTICAL
Accessories Applied by Fabricator	
Ladder & Platform Clips	AS REQUIRED
Insulation Clips & Rings	NO
Vessel Support	YES

Nozzles and Manways			
Mark	No	Size Inches	Service
AA	1	2	VENT
AB	1	24 ID	MANWAY
AC	1	8	HCBN OUTLET
AD	1	2	WATER INLET
AM	1	24 ID	MANWAY
AN	1	24 ID	MANWAY
AU	1	6	RELIEF
BB	1	24 ID	MANWAY
CB	1	24 ID	MANWAY
BD	1	8	HCBN INLET
BL	2	2	LG
BM	2	2	LT
BN	1	2	PI
BS	1	2	STEAMOUT
BT	1	2	UTILITIES
CD	1	4	AQUEOUS OUTLET
X	1	3	INLET
Y	1	3	TO ANALYZER
Z	1	2	FROM ANALYZER

Class	- (NOTE 4)
	- ASME CL300
Facing	- RAISED FACE

Normal Liquid Level	=	LIQUID FULL
Specific Gravity	=	1.0 (WATER)
		0.85 (HYDROCARBON)
Delta-P Vessel(Total)	=	0.20 kg/cm2




NOTES:

- 600 MM THICK COALESCER. STYLE A: STAINLESS STEEL TYPE 304 (SEE STANDARD SPECIFICATION 3-35) SUPPORT PER DWG 3-264.
- VESSEL SHALL BE CONSTRUCTED IN ACCORDANCE WITH UOP STANDARD SPECIFICATION 3-15.
- DISTRIBUTOR PER DWG 3-313 AND DETAIL BELOW. PROVIDE 650 (TOTAL) 6mm DIA. HOLES TO BE 45 DEG BELOW HORIZONTAL CENTERLINE, AND AT BOTTOM, STAGGERED EITHER SIDE OF VERTICAL CENTERLINE AND SPACED EQUALLY.
- FLANGE CLASS DETERMINATION ASSUMES DUAL STAMPED 304/304L MATERIAL IS USED. IF THIS IS NOT THE CASE, THE DESIGN PRESURE AT THE BOTTOM OF THE VESSEL (AFTER CONSIDERATION OF THE LIQUID STATIC HEAD) EXCEEDS THE 150# FLANGE CLASS LIMITS AND 300# FLANGES WILL BE REQUIRED.

PROJECT SPECIFICATION

963765 - 301 SHEET 4 / 9

REV	DATE	BY	APP'D	REV	DATE	BY	APP'D
0	27APR12	TS	HDT				
1	03JUL12	JG	HDT				
2	07SEP12	JG	HDT				

DISTRIBUTOR DETAIL
(HCBN INLET)

ORIENTATION

Drawings Referred to in this Specification

3-122	3-313	3-264			
-------	-------	-------	--	--	--

NOTE - The information in this document is confidential and the property of UOP, LLC and must not be disclosed to others or reproduced in any purpose whatsoever without its written permission.

Revision
Indication



PROJECT SPECIFICATION

963765 — 307

SHEET 5 / 9



**TRAYS AND PACKING
(RANDOM AND STRUCTURED)**

REV	DATE	BY	APVD	REV	DATE	BY	APVD
0	05Jul12	HDT	MEH				

**UOP Phenol Process Unit
Oxidation Section**

Item Number	Service	Sheet
	General Notes	6 & 7
V-2201	Feed Wash Column	8
	Tray Data	9

Other specifications
referenced in this
specification:

UOP Standard Specification: 3-18

UOP Standard Drawing: 3-280, 3-311

UOP Project Specification: 963765-301

Note: The information in this document is confidential and the property of UOP LLC and must not be disclosed to others or reproduced in any manner or used for any purpose whatsoever without its written permission.



PROJECT SPECIFICATION

963765 — **307**

SHEET 6 / 9



**TRAYS AND PACKING
(RANDOM AND STRUCTURED)**

REV	DATE	BY	APVD	REV	DATE	BY	APVD
0	05Jul12	HDT	MEH				

The following general notes apply to all items listed on individual specification sheet:

- A. All items shall comply with the requirements, terms and conditions of this Project Specification and UOP Standard Specification 3-18. For details of vessels see UOP Project Specification 301.
- B. All trays are numbered from **TOP #1 TO BOTTOM**.
- C. Abbreviations: CS = carbon steel; Type 410 = 13% chromium alloy; Type 304 = 18% chromium -8% nickel alloy; Type 316 = 16% chromium – 12% nickel alloy; "M.R." or "MR" = manufacturer's and / or contractor's responsibility. SS may be any of the following – Type 410, Type 304 or Type 316. See UOP Standard Specification 3-18 for additional clarification on materials.
- D. When system of measurement is metric, all dimensions are in millimeters except as noted.
- E. For vessels where the inside diameter is indicated to be minimum (min), adjustments in tray dimensions to accommodate the final inside diameter selected shall be to the chord height of side downcomers which are also indicated as minimum (min).
- F. Vessel nozzle and internals orientation errors are a common source of problems for trayed columns. UOP does not supply specific orientation drawings in order to allow flexibility to the contractor, the vessel fabricator and the internals supplier. The contractor is to ensure sufficient communication between the various parties to avoid orientation difficulties. Some common orientation restrictions follow.
 - Thermowells that are inserted into trayed distillation columns must not contact internals such as support rings or downcomer panels.
 - Reboiler return nozzles should be oriented to minimize vapor interaction with the liquid from the bottom tray traps.
 - Adjacent distillation column trayed sections normally have specific orientation requirements to facilitate vapor and liquid movement between the sections. The supplier of the vessel internals (trays and packing) must provide the vessel fabricator with orientation drawings.
 - Nozzles shall not be located in downcomers.

The following notes apply only when listed for individual item of specification sheet:

1. One pass.
2. Two pass, center downcomers.
- 2x. Two pass, side downcomers.
3. Three pass.
4. Four pass, intermediate downcomers.
- 4x. Four pass, side and center downcomers.
5. Tray(s) shall be liquid tight by seal welding, except at manway(s) where gasketing shall be used.
6. Tray(s) including downcomer(s) shall be liquid tight by seal welding, except at manway(s) where gasketing shall be used.



PROJECT SPECIFICATION

963765 — 307

SHEET 7 / 9



**TRAYS AND PACKING
(RANDOM AND STRUCTURED)**

REV	DATE	BY	APVD	REV	DATE	BY	APVD
0	05Jul12	HDT	MEH				


7. Do not provide drain holes. Tray(s) shall be liquid tight.
8. Stiffeners and support members transverse to the liquid flow direction shall not exceed 2" (50 mm) in depth and shall not be located above upcomers, or within a lateral distance from upcomers equal to one tray space.
9. Trays shall be assembled on rods and spacers or arranged in cartridges with trap attached to downcomer of bottom tray. Furnish Teflon or metal wall wiper at each tray for liquid seal.
10. All tray assemblies shall be designed for installation and removal from top and bottom.
11. Each tray shall have froth initiator(s) in accordance with UOP Standard Drawing No 3-130.
12. Bubble caps shall be in accordance with UOP Standard Drawing No _____ Type No _____.
13. Ceramic Fiber gasketing shall be used as required for proper design and installation of tray(s), manway(s) and / or distributors for packed beds.
14. Each tray shall have a total of ____ — mm diameter holes on approximately mm equilateral triangular pitch.
15. Each tray shall be designed for an upward pressure differential of ____.
16. Drawoff well(s) on tray No ____ shall be ____ deep and a minimum of ____ wide and extend under entire downcomer area.
17. Provide an additional ____ percent of the required random packing to cover losses.
18. Minimum thickness of tray components is 12 gauge (0.104" / 2.6 mm). A corrosion allowance is not required.
19. Bolts and nuts for trays shall be carbon steel (ASTM A307 Grade A for bolts and A563 Grade A for nuts).
20. Tray No(s) ____ shall be designed for a net uplift of 100 pounds per square foot (488 kilograms per square meter).
Tray No(s) ____ shall be designed for a total downward load of 100 pounds per square foot (488 kilograms per square meter) plus dead weight.
21. Customer/Contractor must verify that the structural and mechanical condition of the existing tray(s) and/or tray supports is satisfactory for continuing operation.
22. UOP MD and Slotted Sieve tray decks, downcomers, installation hardware and distributors; and Raschig Super-Rings and distributors are to be supplied by:

Supplier (Mandatory):

UOP LLC
175 East Park Drive
PO Box 986
Tonawanda, NY 14151-0986
Telephone 716-879-7615
Facsimile 716-879-7215

Note: The information in this document is confidential and the property of UOP LLC and must not be disclosed to others or reproduced in any manner or used for any purpose whatsoever without its written permission.

Revision
Indication



PROJECT SPECIFICATION

963765 — **307**

SHEET 8 / 9



**TRAYS AND PACKING
(RANDOM AND STRUCTURED)**

REV	DATE	BY	APVD	REV	DATE	BY	APVD
0	05Jul12	HDT	MEH				
1	14Aug13	CDM	HDT				

Service: Feed Wash Column

Item Number: V-2201

Column Assemblies

Item No	Quan Assem	ID of Vessel	Material	Description	Dwg or Sht No	Dimensions			Tray No	Notes (Sheet 6&7)
1	3	4000	Type 304	Liquid to Liquid Contacting Trays See Note 1 below	5 & 3-311	W = 16" pipe Sch 10	X = 1100	Z = 75	1 - 3	5, 6
2	3	4000	Type 304	Liquid to Liquid Contacting Trays See Note 1 below	5 & 3-311	W = 16" pipe Sch 10	X = 1100	Z = 75	4 - 6	5, 6,
3	1	4000	Type 304	Feed Tray See Note 1 below	5 & 3-311	X = 1100			7	5, 6

Notes:

1. Gasketing materials must be compatible with the process fluid, containing aromatic hydrocarbons and dilute caustic (only Teflon, Neoprene and Viton A are recommended).

Tray sections shall pass through a 24" ID vessel manway.

Note: The information in this document is confidential and the property of UOP LLC and must not be disclosed to others or reproduced in any manner or used for any purpose whatsoever without its written permission.

Revision
Indication



PROJECT SPECIFICATION

963765 — 307

SHEET 9 / 9



**TRAYS AND PACKING
(RANDOM AND STRUCTURED)**

REV	DATE	BY	APVD	REV	DATE	BY	APVD
0	05Jul12	HDT	MEH				
1	14Aug13	CDM	HDT				

Service: Feed Wash Column		Item Number: V-2201	
Tray Data			
Tray Identification (Tray Numbers)	Top (1 - 3)	Middle (4 - 6)	Bottom (7)
Vessel ID, mm	4000	4000	4000
Operating Pressure, kg/cm ²	1.75	1.75 – 4.7	4.7
Operating Temperature, °C	38	38	38
Structural Design Temperature, °C	By Contractor	By Contractor	By Contractor
Fluid Description, Heavy / Light Phases	Water / Cumene	1% NaOH / Cumene	1% NaOH / Cumene
Foam Derating Factor	1.0	1.0	1.0
Heavy Phase - Flow Rate, kg/h (Design for maximum flows shown)	Normal = 3925 Max = 7850	Normal = 12324 Max = 24648	Normal = 12324 Max = 24648
Density, kg/m ³	1000	1000	1000
Light Phase - Flow Rate, kg/h	Normal = 183614 Max = 224009	Normal = 183614 Max = 224009	Normal = 183614 Max = 224009
Density, kg/m ³	847	847	847
Type of Tray	Liquid - Liquid Contacting Trays	Liquid - Liquid Contacting Trays	Liquid - Liquid Contacting Trays
Weir Height, M, mm			
Downcomer Clearance, N, mm			
Total Number of Holes	1548	1548	-
Hole Diameter, mm	6	6	-
Hole Pitch (Triangular), mm	75	75	-
Tray spacing, S, mm (for exceptions see Project Specification 301 Vessels)	3850	3850	3850
Notes			
See UOP Standard Drawing 3-311 for additional tray information			
Tray Layout			
Number of Passes	1	1	1

Maximum allowable overall pressure drop for vessel is 0.2 kg/cm²

Operating pressure of middle and bottom trays includes static head of liquid-full column.

Note: The information in this document is confidential and the property of UOP LLC and must not be disclosed to others or reproduced in any manner or used for any purpose whatsoever without its written permission.